

GENERAL NOTES FOR HISTORIC ITEMS

PROTECTION NOTES FOR THE REMOVAL OF EXISTING PAVEMENT, CURB OR SIDEWALK AND CONSTRUCTION OF NEW PAVEMENT, CURB OR SIDEWALK ADJACENT TO HISTORIC BUILDINGS, CANOPIES, MATERIALS, FENCES, AND RETAINING WALLS

Where proposed work is in proximity to historic buildings or other structures (walls, canopies, retaining walls, fences), and planting beds, and vegetation/groundcover, follow the procedures listed below for demolition, protection, and construction at these addresses:

In the city of MARSHALL, at ALL BLDGS. (list addresses):

1. To minimize potential damage to historic structures and materials, contractor to saw cut existing sidewalk 8 to 12 inches away from the historic structure, canopy supports, fence, or retaining wall.
2. Contractor to construct new sidewalk next to the saw cut edge with installation of expansion joint in between. If existing sidewalk is to be removed entirely, the remaining 8 to 12 inches next to the historic structure, canopy supports, material, fence, or retaining wall will be removed by hand. Expansion joint to be placed between historic structure, canopy support, material, fence, or retaining wall and new sidewalk.
3. Contractor is responsible for preventing damage to historic structure, canopy supports and their awning, materials, fences, retaining walls, including garden elements (planting beds, plantings) during the entire construction project, especially during removal of existing pavement, curb, or sidewalk. During the saw cut and hand removal process, contractor will exercise utmost caution and will physically protect historic structure foundation, canopy supports, materials, elevations, entryways with decorative flooring, fences, retaining walls, and landscape elements.
4. Contractor to repair or replace in kind, at his own expense, any historic materials damaged in the course of executing the work. Contractor is responsible for locating replacement source for historic materials damaged in the course of the work. Texas Historical Commission to be informed of damage and proposed repairs prior to execution of repair work.